



Keith Shuttleworth
&
Associates Limited

**STEAM QUALITY TEST KIT
SQ1E**

**Set Up And
User Guide**

Steam Quality Test Kit SQ1E
User Manual 1.0 ENG
Acknowledgements to EN285

Keith Shuttleworth & Associates Ltd
16 Eaton Green Rd
Luton, LU2 9HE
UK

Table of Contents

Introduction	4
Additional Equipment Requirements	4
Steam Test Points	5
Assembling	5
Non-Condensable Gas Test	6
Dryness Test	8
Superheat Test	10
Health and Safety	11
Care and Maintenance	11
Equipment Specification	11
Appendix 1 (Steam Tables)	Back Cover

Introduction

Thank you for choosing the Keith Shuttleworth & Associates Ltd SQ1E Steam quality kit. This kit was developed through extensive practical experience and has been designed to provide reliable and consistent results that conform to the requirements of EN285.

The Air coolLED non-condensable gas test has been designed to be more robust than the standard equipment and also less dependent upon the skill of the operator. It will be found it will provide results that are more consistent than the EN285 method.

The dryness test equipment is similar to that described in EN285 but has been modified to make easier to use and not require cooling water. Water is a major in both its availability and its potential hazard in a clean room environment . If the calculation disk provided by Keith Shuttleworth Associates Ltd is used, results identical to EN285 will be obtained. The superheat test equipment is identical to that in EN285.

Warning

Before conducting any tests the contents of this manual must be studied in depth and any associated hazards considered. It is stressed that the test methods are defined in EN285 and not by the authors of this manual, and that the current versions of these documents are the primary references. Sterilizer plant rooms are potentially hazardous areas and the tests involve working on live steam. It is assumed by the authors of this manual that staff conducting steam quality testing will be trained and understand the potential dangers involved with respect to burning, due to contact with either steam or hot surfaces or any other related hazards.

Warranty

The Keith Shuttleworth & Associates Ltd Steam Quality Test Kit is designed and manufactured to the highest standards, using top quality materials. A one year parts only warranty applies from the date of delivery to the customer. The warranty does not apply to abuse or misuse of the equipment, or its use outside of the operating parameters defined within this manual.

Additional Equipment Requirements

To enable you to complete the steam tests, additional equipment is required.


1. Two temperature sensors and indicator/recorder capable of measuring over a range of ambient water temperature to maximum steam supply temperature (Typical 0 - 150°C). The sensor used for the superheat test should not exceed 4mm diameter.
2. A balance capable of measuring up to 2Kg with 0.1 g discrimination.
- 3 A mains power source.
4. Approximately 1ltr of water < 27°C per dryness test.

Steam Test Points

In order to test the steam quality specific test points on the steam line are required.

Fig 1 Illustrates the location of the three test points on the steam supply pipe and they are fitted between the steam distribution system and the sterilizer. It is expected that the pressure at this point would be 2-5 barA (30 – 75 psiA).

Fig 1




It is important the pitot tube entry point is level and parallel with the steam pipe as any deviation towards the edge of the pipe can influence the results detrimentally.

Assembling the Steam Test Kit

Non-condensable Gas Kit

- 1 Steam Valve
- 2 Condensate Jug
- 3 Burette
- 4 Water Level up
- 5 Water Level Down
- 6 Flow Pause
- 7 Cooling Temp Indicator
- 8 Power Inlet
- 9 Power Switch
- 10 Steam Inlet



Dryness Kit

- 1 Pitot Tube
- 2 Rubber Tube
- 3 Tube Clamps (Optional)
- 4 Rubber Bung and Tubes
- 5 Flask





Fig 4

Superheat Kit

- 1 Superheat Tube
- 2 Pitot Tube
- 3 Temperature Probe Entry Gland



Non-condensable Gas Test

Setting up

1. Place the air cooled condenser on a level surface with room for the jug under the condensate outlet spout. Ensure there is sufficient space behind the unit to ensure free air flow. Connect the 12V power supply to the power inlet.
2. Isolate the steam supply and after checking that no residual pressure is present, connect the steam supply hose to the non-condensable gas take off point (Fig. 1). Take care, as the steam pipe may be hot and residual steam may be present. Connect the other end of the steam hose to the steam connection of condensing unit (see Fig. 3). Turn the steam supply back on. Warning the steam pipe hose will be hot.

Performing the Test

1. Before starting the test ensure the steam valve is closed.
2. Turn on the power switch at the back of the unit. The unit will perform a brief initialisation sequence and when ready the front panel strips will light up.
3. Slowly open the steam valve. Condensate will start issuing from the outlet spout. Adjust the steam valve to achieve the desired flow rate of condensate. The fans will automatically adjust to the cooling load. The bar graph on the control panel will indicate the current cooling temperature. e.g. as the temperature rises the bars will increase in number. Ensure that the flow does not cause the top bars to turn red. (See additional notes). There is no minimum temperature.
4. Using the Up / Down buttons raise and lower the water level in the burette to your desired level.
7. Ensure that the sterilizer chamber is empty except the normal furniture etc. Select a porous load/equipment cycle and start a run.
8. When the steam supply to chamber first opens, ensure the measuring cylinder is empty. Note you can use the pause button || to stop the flow while you empty the cylinder to prevent drips. Either press and hold or double press to keep the flow stopped. Press || enable the flow again.

9. Zero using the up / down buttons or make a note of the water level.

10. Any non-condensable gases present in the steam being sampled will rise to the top of the burette. The overflow formed by the condensate and the water displaced by the gases, will collect in the measuring cylinder.

11. When at least 100ml of condensate has been collected in the measuring cylinder note the volume of gas collected in the burette (V_G) and the volume of water collected in the measuring cylinder (V_C).

12. Calculate the amount of non-condensable gases as follows in ml per 100 ml of collected condensate using the following formula:-

$$C_{NCG} = \frac{V_G}{V_C - V_G} \times 100$$

C_{NCG} = Content of Non-condensable gases, in ml per 100 ml condensate from steam

V_G = Volume of water displaced from the burette, in ml

V_C = Volume of water collected in the graduated cylinder, in ml

Acceptance Criteria

The test should be considered satisfactory if the level of non-condensable gases does not exceed 3.5 ml of non-condensable gases per 100 ml of collected condensate.

The test should be done at least three times and the maximum result shall comply with the requirements specified.

Additional Notes on the use of the SQ1E condenser

1 On power up the unit checks if it has at low enough coolant temperature. The LED Bars indicate the current internal temperature. If the unit fails to light the front strips it may be because the temperature is too high. Leave the unit to cool its self. If after 40 seconds the unit fails to cool its self its will show over temperature fault.

2 On power up and in operation it may detect a fault. There are 2 fault states:-

- Over temperature. The top two LED bars will flash. Power cycle the unit to reset.
- Fan failure. The 3rd and 4th Led from the top will flash. Power cycle the unit to see if the fault goes away. If it does not contact your supplier for help.

3 You can pause the condensate flow by either pressing and holding the pause button || or you can double click it to lock it in pause. Click the button again to release this mode. This method is recommended when taking readings or emptying the measuring cylinder.

Dryness Test

Setting up Assemble the apparatus as per Fig. 4

Isolate the steam supply and after checking that no residual pressure is present, insert a temperature sensor entry gland into the fitting on the steam pipe. The steam pipe may be hot and precautions should be taken against both burning and the presence of residual steam. The temperature probe should be at the geometric center of the steam pipe. Insert the appropriate size pitot tube (see Table 1 below for the correct size and read the note below) into the steam supply. Turn the steam supply back on, taking the necessary precautions against burning/scalding from the steam that will issue from the pitot tube.

Table 1	Steam Pressure (barA)	Up to 3	Up to 4	Up to 7
		mm	0.8	0.6

Note - Important!

Analysis of the Dryness Value calculation shows that while it takes account of the heat gain by the test equipment, it does not allow for heat losses to the environment which increase with increasing test duration. The longer the test proceeds, the greater the adverse impact on the test result (lower dryness value results). The test duration is affected by the starting volume and temperature of the water in the flask, together with the steam supply pressure and the size of pitot tube used. Our experience is that tests of a short duration are less affected by this effect and we strongly recommend the use of a 0.8 mm pitot tube up pressures of 5 barA and the 0.6 mm size for higher pressures. NB. This approach minimises the unaccounted for losses and does not/cannot provide an artificially high test result.

Performing the Test

1. Weigh the whole assembly including pipe and clips and note the mass in kg (Me).
2. Remove the stopper and tube assembly and pour 650 +/-50 ml of cold water (below 27°C) into the flask. Replace the stopper and tube assembly, weigh the flask and record the mass in kg (Ms).
3. Support the flask close to the pitot tube taking care to avoid the issuing steam. Ensure that the rubber tube and flask are protected from excess heat and draughts. Do not connect it to the pitot tube yet.
4. Introduce the second temperature sensor through the shorter of the two pipes into the water in the flask. Agitate the flask and note the temperature of the water in the flask (To).
5. Ensure the sterilizer is empty except for the usual chamber furniture. Select and start a porous load/equipment cycle.
6. When the steam supply valve to the chamber first opens, connect the rubber tube to the pitot tube. This will require the tester to be in close proximity to the steam issuing from the pitot tube and extreme care is required to avoid scalding and/or burning. Gloves, overalls and eye protection must be worn.

7. Observe/record the steam temperature for the duration of the test and on completion of the test calculate the average temperature (T3).

8. When the temperature in the flask is approximately 80° C, disconnect the rubber tube from the stainless steel tube taking the same precautions as when fitting. Agitate the water in the flask to make sure it is thoroughly mixed. Note the temperature of the water (T1).

9. Remove temperature probe and weigh the flask and stopper assembly including pipe and clips and note the mass in kg (Mf)

10. Calculate the dryness value by using the following formula.

$$D = \frac{(T_2 - T_1) [C_{pw} (m_s - m_e) + A]}{L(m_f - m_s)} - \frac{(T_3 - T_2) C_{pw}}{L}$$

Where:

L = Latent heat of dry saturated steam at temperature T3 (kJ/kg) see Appendix 1

Me = The mass of vacuum flask and rubber stopper assembly, pipes and tube in kg

Ms = The mass of vacuum flask, water charge, rubber stopper assembly, pipes and tube in kg

Mf = The mass of vacuum flask, water charge, condensate, rubber stopper assembly, pipes and tube in kg

T1 = Initial temperature of the water in the vacuum flask in degrees Celsius

T2 = Final temperature of the water in the vacuum flask in degrees Celsius

T3 = Temperature of saturated steam delivered to the sterilizer in degrees Celsius

Cpw = Specific heat capacity of water (4.18 kJ/kg · K)

A = The effective heat capacity of the apparatus (0.23 kJ/K).

If a computer-spreadsheet is to be used then this formula can be used in H17, as in this example spreadsheet.

$$=(((H9-H7)*(4.18*(H3-H1)+0.23))/(H13*(H5-H3)))-((4.18*(H11-H9))/H13)$$

	A	B	C	D	E	F	G	H
1	Total weight of flask etc							0.80938
2								
3	Total weight of flask and 250ml of water							1.43946
4								
5	Total weight of flask + condensate							1.50917
6								
7	Initial temperature of water in flask							22.5
8								
9	Final temperature of water and condensate							77.5
10								
11	Average temperature delivered to sterilizer							144
12								
13	Latent heat of average temperature of steam delivered to sterilizer							2132.6
14								
15								
16								
17	Dryness fraction							0.955

Note! The formula has been modified from the default value of $A = 0.24 \text{ kJ/K}$ to 0.23 kJ/K to account for the use of a stainless steel flask and dip tubes instead of glass, as detailed in EN285.

Acceptance Criteria The test should be considered satisfactory if the following requirements are met:

The dryness value is equal to or greater than 0.95 and at least three tests are conducted.

The Superheat Test

Setting up

1. Assemble the apparatus as per Fig. 5
2. Isolate the steam supply and after checking that no residual pressure is present, insert a temperature sensor entry gland into the fitting on the steam pipe. The steam pipe may be hot and precautions should be taken against both burning and the presence of residual steam. The temperature probe should be at the geometric centre of the steam pipe. Insert the 0.8 mm pitot tube (= nominal 1 mm). Turn the steam supply back on, taking the necessary precautions against burning/scalding from the steam that will issue from the pitot tube.

Insert a temperature sensor through the entry gland of the expansion tube and position it so the sensing point of the thermocouple element is in the geometric centre of the expansion tube. Push the expansion tube onto the pitot tube taking the necessary precautions. This will require the tester to be in close proximity to the steam issuing from the pitot tube and extreme care is required to avoid scalding and/or burning. Gloves, overalls and eye protection must be worn.

Performing the Test

1. Ensure the sterilizer chamber is empty except for the usual chamber furniture. Select and start a porous load/equipment cycle.
2. From the measured temperatures, note the average temperature in the steam service pipe (for use in the dryness test) and in the expansion tube (T_e) when the steam supply to the chamber first opens.
3. Calculate the superheat in $^{\circ}\text{C}$ from the following equation.

$$\text{Superheat} = T_e - T_0$$

Where T_0 is the boiling point of water at local atmospheric pressure.

Acceptance Criteria

The test should be considered satisfactory if the superheat measured in the expansion tube does not exceed 25°C and the temperature measured in the steam pipe did not differ by more than 3°C from that measured in the steam pipe during the steam quality.

Note Negative temperatures are normal.

Health and Safety

Care should always be taken when working on or near steam pipes due to the very high temperatures involved. Thermal gloves, overalls that cover arms and eye protection must be used.

While every effort has been made to provide protection from the extreme temperatures, care should be taken when testing with this equipment.

Do not plug or restrict the "Cooling Out" now as this may pressurize the heat exchanger. Which it has not been designed for.

Do not look into the condensate collection cylinder while the steam valve is open. as hot condensate and/or steam could be ejected.

The submersible pump is electrically powered and care must be taken to prevent hazards arising from the use at electricity in a potentially wet environment.

Care and maintenance

No special care is required for the steam test kit.

Should difficulty be found in obtaining a replacement or any other components, please contact your local Distributor in the first instance or Keith Shuttleworth & Associates Ltd for replacements.

Equipment specifications:

Non-condensable gas test kit	0-12% N/C per 100ml condensed steam
Dryness test	Full range
Superheat test	Full range
Condensing unit (Steam side)	Max 5 barG at 160C
Steam supply tube	Max 10 barG Steam
Pitot Tubes	Max 6 barG at 165°C

Appendix 1

Temp Deg C	Latent Heat	Temp Deg C	Latent Heat	Temp Deg C	Latent Heat	Temp Deg C	Latent Heat
120	2202.42	130	2174	140	2144.59	150	2114.06
120.2	2201.86	130.2	2173.43	140.2	2143.99	150.2	2113.44
120.4	2201.3	130.4	2172.85	140.4	2143.39	150.4	2112.82
120.6	2200.74	130.6	2172.27	140.6	2142.79	150.6	2112.19
120.8	2200.18	130.8	2171.69	140.8	2142.19	150.8	2111.57
121	2199.62	131	2171.11	141	2141.59	151	2110.95
121.2	2199.06	131.2	2170.53	141.2	2140.99	151.2	2110.32
121.4	2198.49	131.4	2169.95	141.4	2140.39	151.4	2109.69
121.6	2197.93	131.6	2169.37	141.6	2139.79	151.6	2109.07
121.8	2197.37	131.8	2168.79	141.8	2139.18	151.8	2108.44
122	2196.81	132	2168.21	142	2138.58	152	2107.81
122.2	2196.25	132.2	2167.62	142.2	2137.98	152.2	2107.19
122.4	2195.68	132.4	2167.04	142.4	2137.37	152.4	2106.56
122.6	2195.12	132.6	2166.46	142.6	2136.77	152.6	2105.93
122.8	2194.55	132.8	2165.87	142.8	2136.16	152.8	2105.3
123	2193.99	133	2165.29	143	2135.56	153	2104.67
123.2	2193.43	133.2	2164.71	143.2	2134.95	153.2	2104.04
123.4	2192.86	133.4	2164.12	143.4	2134.34	153.4	2103.41
123.6	2192.3	133.6	2163.54	143.6	2133.74	153.6	2102.78
123.8	2191.73	133.8	2162.95	143.8	2133.13	153.8	2102.15
124	2191.16	134	2162.37	144	2132.52	154	2101.51
124.2	2190.6	134.2	2161.78	144.2	2131.91	154.2	2100.88
124.4	2190.03	134.4	2161.19	144.4	2131.3	154.4	2100.25
124.6	2189.46	134.6	2160.61	144.6	2130.69	154.6	2099.61
124.8	2188.9	134.8	2160.02	144.8	2130.08	154.8	2098.98
125	2188.33	135	2159.43	145	2129.47	155	2098.34
125.2	2187.76	135.2	2158.84	145.2	2128.86	155.2	2097.71
125.4	2187.19	135.4	2158.25	145.4	2128.25	155.4	2097.07
125.6	2186.62	135.6	2157.66	145.6	2127.64	155.6	2096.44
125.8	2186.05	135.8	2157.07	145.8	2127.03	155.8	2095.8
126	2185.48	136	2156.48	146	2126.42	156	2095.16
126.2	2184.91	136.2	2155.89	146.2	2125.8	156.2	2094.52
126.4	2184.34	136.4	2155.3	146.4	2125.19	156.4	2093.89
126.6	2183.77	136.6	2154.71	146.6	2124.58	156.6	2093.25
126.8	2183.2	136.8	2154.12	146.8	2123.96	156.8	2092.61
127	2182.63	137	2153.53	147	2123.35	157	2091.97
127.2	2182.06	137.2	2152.93	147.2	2122.73	157.2	2091.33
127.4	2181.48	137.4	2152.34	147.4	2122.12	157.4	2090.68
127.6	2180.91	137.6	2151.75	147.6	2121.5	157.6	2090.04
127.8	2180.34	137.8	2151.15	147.8	2120.88	157.8	2089.4
128	2179.76	138	2150.56	148	2120.26	158	2088.76
128.2	2179.19	138.2	2149.96	148.2	2119.65	158.2	2088.11
128.4	2178.61	138.4	2149.37	148.4	2119.03	158.4	2087.47
128.6	2178.04	138.6	2148.77	148.6	2118.41	158.6	2086.83
128.8	2177.46	138.8	2148.18	148.8	2117.79	158.8	2086.18
129	2176.89	139	2147.58	149	2117.17	159	2085.54
129.2	2176.31	139.2	2146.98	149.2	2116.55	159.2	2084.89
129.4	2175.74	139.4	2146.39	149.4	2115.93	159.4	2084.24
129.6	2175.16	139.6	2145.79	149.6	2115.31	159.6	2083.6
129.8	2174.58	139.8	2145.19	149.8	2114.69	159.8	2082.95